

Office of the Collector Panna Dist. Panna (M.P.)

Sr. No./Janbhagidari/09/.....

Panna Date.....



N.I.T. for Construction of Shopping Complex, C.C. Road, Side Drain and other related Development work at P.H.C. Compound Gunour, Dist.- Panna (M.P.)

Sr. No.	Particulars of Items	Qty.	Rate
1	S.O.R. (1) P-8 Excavation in all types of soils for all types and sizes of foundation and drains including disposal of excavated stuff up to 50 M lead and a left up to 1.5 M including dressing and leveling of pits and disposed stuff as directed by engineer in charge.	172.94	30.00
2	S.O.R. (3) P-8 Excavation in soft rock for all types and sizes of foundation and drains including disposal of excavated stuff up to 50 M lead and a left up to 1.5 M including dressing and leveling of pits and disposed stuff as directed by engineer in charge.	48.60	103.00
3	S.O.R. (1 A-b) P-17 Providing and laying mechanically mixed cement concrete 1:4:8 with crushed stone aggregate excluding cast of centering & shuttering with 40m.m nominal size graded stone aggregate.	48.66	1293.75
4	S.O.R. 1 (b) P-23 Providing and laying mechanically mixed reinforcement cement concrete excluding centering, shuttering and reinforcement in foundations, plinth and in superstructure upto a height of 4.0 m. above plinth level (M-20)	78.23	2212.50



5	S.O.R. 1 (a) P-13		
(i)	Providing and fixing form work i/c centering, shuttering, strutting staging, propping bracing etc. complete and including its removal for Foundation, footings, base of columns and plinth Beam in any shape and size up to plinth level.	196.91	56.00
(ii)	S.O.R. 2 (ii) P-13 Providing and fixing form work i/c centering, shuttering, strutting staging, propping bracing etc. complete and including its removal upto a height of 4m above plinth level.	144.72	77.00
(iii)	S.O.R. 2 (i-ix) P-13 Providing and fixing form work i/c centering, shuttering, strutting staging, propping bracing etc. complete and including its removal upto a height of 4m above plinth level.	266.75	120.00
(iv)	S.O.R. 2 (v) P-13 Providing and fixing form work i/c centering, shuttering, strutting staging, propping bracing etc. complete and including its removal upto a height of 4m above plinth level. Vertical and horizontal fins individually or forming box, louvers, bands, almarish shelves and likes.	49.90	130.00
6	S.O.R. 8 P-24 Providing and placing in position cold twisted steel and hot rolled deformed steel reinforcement for R.C.C. work including cutting, Bending, Binding etc. complete as per Drawings including cost of Binding wire and Including all Wastages etc. complete.	6141.00 Kg.	38.40

521.15 Cum. x 0.785



7	S.O.R. 19 P-31 Coursed rubble masonry (second sort) with hard Stone in foundation and plinth in cement mortar 1:6 (1Cement: 6 sand)	115.19	1050.00
8	S.O.R. 17 P-11 Providing and filling in plinth with sand/Crusher Dust and hard moored under floor, including watering ramming, consolidation, dressing and cost of all labor, materials, T& P etc complete. Required for the work C.C. 1:4:8 + R.C.C. M-20 + C.R. Masonary 95.00+138.99+103.24		
9	S.O.R. (3a+5) P-38 Brick work with well burnt open bhatta brick crushing strength not less than 20kg /sqcm and water absorption not more than 25% with cement mortar 1:8	354.98	200.00
10	S.O.R. 10 (b) P-39 Brick work 10 C.M. with well burnt chimney bricks in bull patent Trench Kiln manufactured by Ghol Process crushing strength not less than 25Kg./Sq.cm. and water absorption not more than 20% in superstructure upto 4.0 M. height above plinth level. (b) Cement Mortar 1:4 (1Cement : 4 Sand)	56.82	1528.75
11	S.O.R. 7 P-75 Supplying and fixing rolling shutter of approved makes made of 80×1.25mm M.S. laths interlocked together their entire length and jointed together at the end by end locks mounted on specially designee pipe shaft with brackets side guides and arrangements for inside and out side locking with push and pull operation complete but excluding the cost of top cover and spring	94.35	992.00



12	S.O.R. 8 P-75 Providing and fixing 27.5cm. long wire spring for rolling shutters	20.00	272.00
13	S.O.R. 10 P-75 Providing and fixing ball bearing for rolling shutter	20.00	156.80
14	S.O.R. 9 P-75 Providing and fixing top cover for rolling shutter	40.00	88.00
15	S.O.R. 25 (c) P-120 Chequered Terrazo tiles 22 MM thick with Marble chips of size upto 6 MM in floors on 25 MM thick bed of cement mortar 1:6 joint with cement slurry mixed with pigment to match the shade of tiles including grinding, rubbing & polishing complete. Dark shade using ordinary cement.	50.00	290.00
16	S.O.R. 3 (b) P-74 Steel work welded in built-up section trusses and framed work i/c cutting, hoisting and fixing in position and applying a priming coat of red lead paint. In flat Iron, Tees, Angles, Channels and M.S. Squire/round bars.	81.20	33.50
17	S.O.R. 3 (b) P-74 Steel work welded in built-up section trusses and framed work i/c cutting, hoisting and fixing in position and applying a priming coat of red lead paint. In flat Iron, Tees, Angles, Channels and M.S. Squire/round bars.	650.00 Kg.	44.80



18	S.O.R. 1(c) P-107 12mm thick plastering in CM 1:6 Plain sides of walls.	657.34	37.50
19	S.O.R. 2(c) P-107 15mm thick plastering in CM 1:6 Rough sides of walls. Qty 1 same as per above item no 20.	649.44	43.75
20	S.O.R. 15 P-133 Finishing wall with water proofing cement paint of required shade on new work.	1525.50	25.00
21	S.O.R. 2(a) P-17 Providing and laying C.C. M-15	3.15	1868.75
22	S.O.R. 41 P-124 Providing and fixing 40MM thick find desk stone over drains	63.00	182.00
23	S.O.R. 41 (i) (P-20) Construction of granular sub base by providing course graded material spreading in uniform layers with on prepared surface mixing by mixing place method at O.M.C. and compacting with vibratory roller to achieve the desired density complete in all respect and as per relevant clauses of section -400.	200.00	505.00
24	S.O.R. 6.5 Page-26 Construction of base / sub base using cement, sand, fly ash and course aggregate proportioned as per table 4 of I.R.C. 74/1979 and with water content ratio, stamp and compressive strength as defined in the said table mix prepared in a batching and mixing, plant transported to site, laid with paver with electronic sensor and compacted with a vibratory roller 8-10 tonnes capacity within the time limit laid down vide clauses 7.6.3 of I.R.C. 74-1979 and as per approved plans and as per relevant clauses of section - 600.	150.00	1738.00



25	S.O.R. 6.7 Page 27 Construction of dowel jointed, plain cement concrete pavement in M-40 grade concrete over a prepared sub base with 43 or higher grade cement, course and fine aggregate conforming to 1.5. 383 maximum size of course aggregate not exceeding 25 mm Replacing cement by fly ash to the extent of 15% and sand by 10% mixed in a botching and mixing plant per approved mix design. Transported to site, laid with a fixed form or slip form paver with electronic, sensor, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filter, separation membrane sealant primer joint sealent debonding strip, placing of dowel bar and tie rod. admixtures a approved curing compound. Finishing to lines, and grade as per relevant clauses of section. Boo but excluding cast of steel in dowel bar and the rod etc.		
26	S.O.R. 62 P.- 127 Providing and fixing 6mm thick glazed tiles as per specification	200.00	4127.00
27	S.O.R 2 P.- 107 12mm thick plaster in CM 1.4 with neat cement flooring	127.40	540.00
28	S.O.R. 4(a) P.- 107 6mm thick plaster in CM 1.3	75.00	50.00
		210.00	77.50

Note : The above N.I.T. Belong to MPPWD SOR issued by Engineer in chief M.P. P.W.D. Bhopal on date 01-11-1999 including amendment 15-04-2008 and amendment till the date of issuing this tender for building works and S.O.R. issued on 01-04-08 and amendment upto date of issuing the tender for Road works M.P.P.W.D.

Prepared by: (Consultant)
for: Shri (Partner)
M/s Shri Consultancy Panna
Panna (M.P.)
Reg.No.- 06/11/01/00019/07

Approved by
Collector Panna
Distt. Panna (M.P.)

P.H.C. Gunour

3.00x4.00m
1.50m Ver.

→ To Barachh

Road

10 | 9 | 8 | 7 | 6 | 5

G

4
3
2
1

Stadium Of H.S.School



Conceptionl Plan For Shopping Complex
At P.H.C. Compound Gunour Panna M.P.

To Gunour Town →

CONSULTANT,

Panshastri
2.2.09
M/s. SHRI CONSULTANCY, PANNAR

Shukla

एफिसल
राजी कल्याण समिति
राज्य राज. केन्द्र राजी (पन्ना)

CA

राज्य राज. केन्द्र राजी (पन्ना)
एफिसल
राजी कल्याण समिति

Shukla

राजी कल्याण समिति
राज्य राज. केन्द्र राजी (पन्ना)